

Addendum #2

Love's Drive, CR 17 & US 20 EB Ramps Intersection Improvement

August 3, 2017

The project bid documents and specifications have been modified and/or clarified as follows:

- 33" Concrete Median Barrier: The cost of the removal of the existing wall is added as item # 97 – Structures and Obstructions, Remove.
- The cost for the 15 feet of 12" pipe should be included in the pay item for inlet type H.
- K inlets are shown on the South side of Loves Drive on Sheets 21 and 22.
- Loves Drive Storm: Storm structures are on Loves Drive and are accounted for including, but not limited to, ten (10) Elkhart County Precast Storm CB w/inlet type frame & grate and two (2) Type K inlets with type 10 frame & grate.
- Item No. 30 (Type 13 Casting – 2 EA) should be revised to be Type 10 Casting – 2 EA
- The Type MS end treatment is to attached to the end of the concrete median wall as shown on Sheet 26.
- The project will be paid based on the line items contained in the bid sheet. This is not a lump sum bid.
- The project is considered a balance project. Any material needed should be made available from the adjoining parcel(s) owned by Love's, whether from the retention areas or another adjacent borrow location.
- Items # 91 and 93 do not have quantities listed. Please provide a unit price for each, and the bid form will be adjusted to indicate (1).
- The Bid form will be corrected and posted Friday, 08-04-17 by noon. Please use the corrected bid form. The old form will not be accepted at the time of bid opening.
- Questions of missing items, such as sanitary manholes, or any other missing items. necessary to complete the project will have to be addressed through change order(s).
- Items # 52 (Construction Engineering) and #53 (Mobilization and Demobilization) will be adjusted to a quantity of one (1).
- All signs and traffic markings necessary for the project shall be included in the cost of maintenance of traffic #51.